

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-151-11029-00-01  
Spot: NENWNW Sec/Twnshp/Rge: 26-28S-13W  
4982 feet from S Section Line, 4379 feet from E Section Line  
Lease Name: ED BREHM Well #: 2  
County: PRATT Total Vertical Depth: 4500 feet

Operator License No.: 33851  
Op Name: ONEOK FIELD SERVICES LLC  
Address: 100 W5TH ST MD 16-1  
TULSA, OK 74103

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	10.75	896		WITH 350 SX CMT
L1	2.875	4381	2200	
PROD	5.5	4499	0	WITH 380 SX CMT

Well Type: GSO UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/21/2011 9:00 AM  
Plug Co. License No.: 34082 Plug Co. Name: ALLIANCE WELL SERVICE INC.  
Proposal Rcvd. from: WAYNE JENKINSON (T&C) Company: T & C CONSULTING Phone: (620) 617-5257

Proposed Plugging Method: FREE POINT 2 7/8" LINER @ 2200' +/- PULL LINER OUT OF HOLE. SET CMT RETAINER NEAR TOP OF 2 7/8" LINER. SQUEEZE LOWER SIMPSON PERFS @ 4241'-4246' WITH CMT. FREE POINT & CUT OOF 5 1/2" CASING. LAY DOWN CASING. RUN TBG IN TO SPOT PLUGS. 1ST PLUG ON 5 1/2" CASING STUB WITH 25 SX CMT. 2ND PLUG AT 920' WITH 20 SX GEL & 75 SX CMT. 3RD PLUG AT 300' WITH 75 SX CMT. 4TH PLUG AT 60' WITH 30 SX CMT.

Plugging Proposal Received By: STEVE PFEIFER Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 04/21/2011 9:45 AM KCC Agent: RICHARD LACEY

Actual Plugging Report:

\*\*PERFS FROM 2508-4225 OA ARE SQUEEZED WITH CMT.\*\* SET CMT RETAINER @ 2180'. STUNG INTO RETAINER. PUMPED THROUGH RETAINER WITH 110 SX CMT @ 1000# TO 1700#. PULLED OUT OF RETAINER & PUT 10 SX CMT ON TOP OF RETAINER. PRESSURED TO 5 1/2" TO 900 PSIG & HELD. PERFORATED 5 1/2" @ 920'. PUMPED 350 SX CMT DOWN 5 1/2". CIRCULATED CMT TO SURFACE UP 10 3/4" X 5 1/2" ANNULUS.

Perfs:

Top	Bot	Thru	Comments
4425	4433		
4241	4246		LOWER SIMPSON
3671	3695		
3634	3636		
3242	3245		
3150	3154		
3128	3134		
3054	3060		
2668	2671		
2508	2526		

Remarks: USED 60/40 POZMIX 4% GEL BY BASIC.

Plugged through: TBG

RECEIVED  
APR 25 2011  
KCC WICHITA

District: 01

Signed Richard W. Lacey  
(TECHNICIAN)

RECEIVED  
APR 22 2011  
KCC DODGE CITY

Form 10-273