

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-081-10165-00-01  
Spot: NWNE Sec/Twnshp/Rge: 30-30S-33W  
4656 feet from S Section Line, 1987 feet from E Section Line  
Lease Name: SWLVLU Well #: 23  
County: HASKELL Total Vertical Depth: 4850 feet

Operator License No.: 5447  
Op Name: OXY USA INC.  
Address: 5 E GREENWAY PLZ PO BOX 27570  
HOUSTON, TX 77227

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		4158		
CIBP		4615		
SURF	8.625	741		WITH 650 SX CMT
PROD	5.5	4850	0	WITH 200 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/20/2011 8:00 AM  
Plug Co. License No.: 34069 Plug Co. Name: BASIC ENERGY SERVICES, LP  
Proposal Rcvd. from: TONY ATON Company: OXY USA Phone: \_\_\_\_\_

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: STEVE DURRANT Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 04/21/2011 11:00 AM KCC Agent: KEN JEHLIK

Actual Plugging Report:

**\*\*CASING LEAK 1470-1501'. TOP OF FISH @ 2885' (TBG & RODS LEFT IN)\*\***  
PERFORATED FROM 2876-2877'. SET CMT RETAINER @ 2780'. RUN TBG, STING INTO RETAINER & PUMP 75 SX CMT THROUGH PERFS @ 2876-2877' AT 1 1/2 BPM @ 600#. STING OUT OF RETAINER. ATTEMPT TO CIRCULATE WELL WITH 40 BBLs MUD. WOULD NOT CIRCULATE. PULL TBG TO 1512' & SPOT 50 SX CMT. WELL CIRCULATED. TOOH W/TBG. 4/21/11: TAGGED TOC IN 5 1/2" @ 1014'. PERFOATE AT 760'. CIRCULATE CMT TO SURFACE WITH 200 SX CMT LEAVING THE 5 1/2" CASING & 5 1/2" X 8 5/8" ANNULUS FULL OF CMT.

Perfs:

Top	Bot	Thru	Comments
4754	4770		DES MONIES
4648	4650		KC B
4173	4175		LANSING C
4154	4156		LANSING B2
4152	4158		LANSING B2
4132	4138		LANSING B1
2876	2877		

Remarks: \*\*COMPLAINCE ISSUE: DENIED TA HIGH FL\*\* USED 60/40 POZMIX 4% GEL BY BASIC ENERGY.

Plugged through: TBG

District: 01

RECEIVED  
APR 25 2011  
KCC DODGE CITY

Signed

*Ken Jehlik*  
(TECHNICIAN)

RECEIVED

APR 28 2011

KCC WICHITA

Form CP-2/3