

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-095-01051-00-00
Spot: NWSESW Sec/Twnshp/Rge: 16-28S-5W
990 feet from S Section Line, 3630 feet from E Section Line
Lease Name: HOBBS OWWO Well #: 3
County: KINGMAN Total Vertical Depth: 3848 feet

Operator License No.: 5086
Op Name: PINTAIL PETROLEUM, LTD.
Address: 225 N MARKET STE 300
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	137		85 SX
PROD	5.5	3831		75 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/28/2011 8:00 AM
Plug Co. License No.: 31627 Plug Co. Name: WHITETAIL CRUDE, INC
Proposal Rcvd. from: DON TILLMAN Company: _____ Phone: _____

Proposed Plugging Method: AS PER KCC INSTRUCTIONS.

Plugging Proposal Received By: VIRGIL CLOTHIER Witness Type: PARTIAL
Date/Time Plugging Completed: 03/01/2011 11:00 AM KCC Agent: B. J. HOPE

Actual Plugging Report:

RAN TUBING INTO 3800' - SPOTTED 35 SX CEMENT & 100 LBS HULLS & PULLED TUBING - TAGGED TOP OF CEMENT @ 3750' CASING PERF @ 850' @ 450' & 200'. RAN TUBING IN SPOTTED 35 SX @ 850', RAN TUBING IN SPOTTED 50 SX @ 450'. RAN TUBING IN CIRCUALTED TO SURFACE FROM 200' WITH 35 SX. 3-1-11 CUT HEAD OFF & TOPPED OFF WITH 10 SX OF CEMENT.

Perfs:

Top	Bot	Thru	Comments
3816	3818		

Remarks: DENIED TA PASSED 10 YEARS

Plugged through: TBG

District: 02

Signed

B. J. Hope

(TECHNICIAN)

RECEIVED
APR 27 2011
KCC WICHITA