

TO: ✓
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-155-21467-00-00
Spot: SESESW Sec/Twnshp/Rge: 29-26S-9W
330 feet from S Section Line, 2970 feet from E Section Line
Lease Name: FOSTER Well #: 1-29
County: RENO Total Vertical Depth: 4052 feet

Operator License No.: 31191
Op Name: R & B OIL & GAS, INC.
Address: 912 N LOGAN PO BOX 195
ATTICA, KS 67009

String	Size	Depth (ft)	Pulled (ft)	Comments
<u>SURF</u>	<u>8.625</u>	<u>281</u>		<u>200 SX</u>
<u>PROD</u>	<u>4.5</u>	<u>4048</u>	<u>1500</u>	<u>150 SX</u>

Well Type: OG UIC Docket No: _____ Date/Time to Plug: 02/04/2011 12:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: JEFF KLOCK Company: QUALITY WELL SERVICE Phone: _____

Proposed Plugging Method: AS KCC
REQUIRES

Plugging Proposal Received By: _____ WitnessType: PARTIAL
Date/Time Plugging Completed: 02/11/2010 5:00 PM KCC Agent: B. J. HOPE

Actual Plugging Report:

BOTTOM PLUG PUMED 30 SX CEMENT & 100 LBS HULLS TAGGED BOTTOM PLUG @ 3240'. CUT CASING OFF @ 1520' - PULLED CASING TO 1400' PUMPED 35 SX COMMON CEMENT W/3% CC. PULLED CASING TO 900' - 35 SX SPOTTED. PULLED CASING TO 330' - CIRCULATED TO SURFACE WITH 95 SX CEMENT.

Perfs:

Top	Bot	Thru	Comments
3600	3606		SPF

Remarks: DENIED TA - HIGH FLUID LEVEL

Plugged through: CSG

District: 02

Signed B. J. Hope

(TECHNICIAN)

RECEIVED
APR 27 2011
KCC WICHITA