

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-24310-00-00
Spot: NESESE Sec/Twnshp/Rge: 28-19S-11W
990 feet from S Section Line, 330 feet from E Section Line
Lease Name: BAIRD Well #: 2
County: BARTON Total Vertical Depth: 3362 feet

Operator License No.: 33637
Op Name: STEPCO OIL, INC.
Address: 519 W 6TH ST PO BOX 155
ELLINWOOD, KS 67526

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	254	0	150 SX
PROD	5.5	3337	2300	100 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/11/2011 2:00 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC. Phone: (620) 938-2943

Proposed Plugging Method: Ordered 275 sxs 60/40 pozmix - 4% gel - 500# hulls.

RECEIVED
APR 25 2011
KCC WICHITA

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 04/11/2011 5:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Sanded off perfs and topped with 5 sxs cement.
Cut casing at 2300'.
Pulled casing to 1500' - pumped 125 sxs cement with 300# hulls.
Pulled casing to 600' - pumped 40 sxs cement with 100# hulls.
Pulled casing to 200' - circulated to surface with 65 sxs cement.
Pulled casing - hole stayed full.

Perfs:

Top	Bot	Thru	Comments
3337	3362		OPEN HOLE

Remarks: COPELAND ACID AND CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed Bruce Rodie
(TECHNICIAN) CM

Form CP-2/3

APR 21 2011