

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-053-20025-00-00
Spot: N2SWNWSW Sec/Twnshp/Rge: 20-14S-10W
1854 feet from S Section Line, 4965 feet from E Section Line
Lease Name: BORELL B Well #: 1
County: ELLSWORTH Total Vertical Depth: 3250 feet

Operator License No.: 9408
Op Name: TRANS PACIFIC OIL CORPORATION
Address: 100 S MAIN STE 200
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	350		225 SX
PROD	4.5	2890		100 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/19/2011 2:00 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Revd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE Phone: (620) 727-3409

Proposed
Plugging
Method:

SEE BELOW - NO PERFS LISTED OR MENTION OF ANY CASING LEAKS ON CP-1.

Plugging Proposal Received By: VIRGIL CLOTHIER Witness Type: PARTIAL
Date/Time Plugging Completed: 04/21/2011 10:10 AM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

Perfs:

MIRU, CK BOTTOM. RUN TUBING TO 2780' AND PUMP 40 SX'S CEMENT.
PERFORATE @ 1200', 850' AND 400'. ON 4-20-11 I RAN TUBING TO 1200' AND
PUMPED 35 SX'S CEMENT, PULLED TUBING TO 850' AND PUMPED 35 SX'S, PULLED
TUBING TO 400' AND TIRED TO CIRCULATE CEMENT--COULD NOT. LET SET FOR
2 HR'S CAME BACK AND TAGGED CEMENT AT 1230'. RAN TUBING BACK TO 1200'
AND PUMPED 20 MORE SX'S CEMENT, PULLED TUBING TO 850' AND PUMPED 35
SX'S -- TO COME BACK NEXT DAY AND TAG. TAGGED CEMENT ON 4-21-11 AT
597'. RUN TUBING TO 400' AND PUMPED 40 MORE SX'S TO CIRCULATE CEMENT
TO SURFACE. RAN 1" TUBING ON BACKSIDE TO 212'--WHERE STACKED OUT,
AND CIRCULATED 40 SX'S TO SURFACE. RAN 1" BACK DOWN CASING TO 70'--
WHERE STACKED OUT. AND TOPPED OFF WITH 5 MORE SX'S.

RECEIVED
APR 27 2011
KCC WICHITA

Remarks: 60-40 POZ, 4% GEL, PIONEER WIRELINE #33368. QUALITY #5182. DENIED TA.

Plugged through: TBG

District: 02

Signed

Virgil Clothier
(TECHNICIAN)

RECEIVED
APR 27 2011
Form CP-23
KCC WICHITA

JK