

TO: **STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING**
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-053-20043-00-00
Spot: SENWSE Sec/Twnshp/Rge: 20-14S-10W
1323 feet from S Section Line, 1561 feet from E Section Line
Lease Name: KRATKY Well #: 2
County: ELLSWORTH Total Vertical Depth: 2890 feet

Operator License No.: 9408
Op Name: TRANS PACIFIC OIL CORPORATION
Address: 100 S MAIN STE 200
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	200		150 SXS CMT
PROD	4.5	2889		100 SXS CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/18/2011 9:30 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3409

Proposed Plugging Method: SEE BELOW

Plugging Proposal Received By: JEFF KLOCK Witness Type: PARTIAL
Date/Time Plugging Completed: 04/18/2011 11:30 AM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

Perfs:

MIRU, ATTEMPT TO CK BOTTOM -- ENCOUNTERED OBSTRUCTION--TURNED ON WITH BIT ON TUBING--GOT THRU. PUMPED 40 SX'S CEMENT @ 2760'. PERFORATED @ 1200', 850', AND 250'. RUN TUBING TO 1200' AND PUMP 35 SX'S, PULL TUBING TO 850' AND PUMP 35 SX'S WITH 100#'S COTTON HULLS AND 3% CC. PULL TUBING TO 250' AND CIRCULATE CEMENT TO SURFACE. PULL TUBING OUT AND TOP OFF.

RECEIVED
APR 27 2011
KCC WICHITA

Remarks: 60-40 POZ, 4% GEL. PIONEER WIRELINE #32847. QUALITY TICKET #5180. COMPLIANCE DUE TO DENIED TA.

Plugged through: TBG

District: 02

Signed

Virgil Clothier
(TECHNICIAN)