

TO: ✓
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-053-20267-00-00
Spot: NWSENWNW Sec/Twnshp/Rge: 21-14S-10W
4304 feet from S Section Line, 4363 feet from E Section Line
Lease Name: VOPAT A Well #: 13
County: ELLSWORTH Total Vertical Depth: 2939 feet

Operator License No.: 9408
Op Name: TRANS PACIFIC OIL CORPORATION
Address: 100 S MAIN STE 200
WICHITA, KS 67202

| String | Size | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|-------------|
| SURF | 8.625 | 307 | | 175 SXS CMT |
| PROD | 4.5 | 2938 | | 150 SXS CMT |

Well Type: SWD UIC Docket No: _____ Date/Time to Plug: 04/18/2011 1:30 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3409

Proposed Plugging Method: SEE BELOW. NO PERFS LISTED ON CP-1, OBTAINED THAT INFO FROM RICHARD MCINTYRE.

Plugging Proposal Received By: JEFF KLOCK Witness Type: PARTIAL
Date/Time Plugging Completed: 04/19/2011 9:30 AM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

MIRU, HAD TO WELD COLLAR ON TUBING BROKEN OFF AT WELL HEAD. ESTABLISHED INJ. RATE @ 1 1/4 BB'L PER MINUTE. PUMPED 40 SX'S CEMENT TO COVER PERFS MIX WITH COTTON HULLS. PERFORATED @ 1200' AND PUMPED 40 SX'S COMMON CEMENT - 3% CC-DISPLACED--LET SET, THEN PERFORATED @ 850' AND PUMPED 40 SX'S CEMENT WITH COTTON HULLS--THEN PERFOATED @ 360' AND PUMPED 170 SX'S IN TUBING THEN UP 4.5" CASING--CIRCULATED. DID NOT CIRCULATE UP THE 8.625"--CAME BACK ON 4-19-11 AND RAN 250' OF 1" TUBING DOWN BACKSIDE OF 4.5" AND PUMPED 45 SX'S CEMENT. ADDED 5 SX'S CEMENT BETWEEN TUBING AND CASING TO FILL UP.

Perfs:

| Top | Bot | Thru | Comments |
|------|------|------|----------|
| 2839 | 2853 | CSG | |
| 2458 | 2466 | CSG | |

RECEIVED
APR 27 2011
KCC WICHITA

Remarks: 60-40 POZ, 4% GEL. QUALITY WELL SERVICE #5181. PIONEER WIRELINE #33366. COMPLIANCE DUE TO DENIED TA.
Plugged through: TBG

District: 02 Signed Virgil Clothier
(TECHNICIAN)