

TO: ✓
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-135-22157-00-00
Spot: NWNWSE Sec/Twnshp/Rge: 10-16S-25W
2320 feet from S Section Line, 2237 feet from E Section Line
Lease Name: GIESS D Well #: 3
County: NESS Total Vertical Depth: 4533 feet

Operator License No.: 5030
Op Name: VESS OIL CORPORATION
Address: 1700 WATERFRONT PKWY BLDG 500
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	287		WITH 190 SX CMT
PC		1965		WITH 400 SX CMT
PROD	5.5	4507	0	WITH 200 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/21/2011 1:00 PM
Plug Co. License No.: 32938 Plug Co. Name: NORTH FORK WELL SERVICE LLC
Proposal Rcvd. from: JOE RUPP Company: VESS OIL CORPORATION Phone: (785) 798-5151

Proposed Plugging Method: RUN TBG TO 3506' & SPOT 50 SX CMT & 150# HULLS. PULL TBG TO 1900' & PUMP CMT UNTIL IT CIRCULATES. PULL TBG & TOP OFF. TIE ONTO BACKSIDE & PUMP 50 SX CMT IF POSSIBLE.

Plugging Proposal Received By: MICHAEL MAIER Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 04/21/2011 4:00 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

TBG, RODS, & PUMP STUCK IN HOLE @ 3700' SANDED IN. RAN TBG TO 3506' & PUMPED 50 SX CMT & 150# HULLS. PULLED TBG TO 1900' & PUMPED 185 SX CMT. CMT CIRCULATED THEN FELL BACK. PULLED TBG & TOPPED OFF WITH 50 SX CMT. DID NOT STAY. TIED ONTO BACKSIDE & PRESSURED UP. 4/22/11: FOUND CMT DOWN 350'. TOPPED OFF WITH 40 SX CMT. CASING STAYED FULL.

Perfs:

Top	Bot	Thru	Comments
4507	4533		MISS. DOLOMITE
1965			

Remarks: **COMPLIANCE ISSUE: DENIED TA HIGH FL** USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: TBG

District: 01

RECEIVED
APR 26 2011
KCC DODGE CITY

Signed

Michael Maier

(TECHNICIAN)

RECEIVED
APR 28 2011
KCC WICHITA

Form CP 2/3