

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-101-21379-00-01
Spot: N2N2SW Sec/Twnshp/Rge: 10-16S-30W
2327 feet from S Section Line, 3807 feet from E Section Line
Lease Name: YORK (OWWO) Well #: 1
County: LANE Total Vertical Depth: 4466 feet

Operator License No.: 31251
Op Name: WABASH ENERGY CORPORATION
Address: RR # 1 BOX 180A PO BOX 595
LAWRENCEVILLE, IL 62439

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	243		WITH 170 SX CMT
PC		2127		
PROD	5.5	4462	0	WITH 170 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/05/2011 8:30 AM
Plug Co. License No.: 32810 Plug Co. Name: PROFESSIONAL PULLING SERVICES LLC
Proposal Rcvd. from: E.L. WHITMER, JR. Company: WABASH ENERGY Phone: (618) 943-6451

Proposed Plugging Method: PUMP 5 SX GEL THEN 40 SX CMT & 150# HULLS ON BOTTOM. PULL TBG TO 2150' & CIRCULATE CMT. PULL TBG & TOP OFF. TIE ONTO BACKSIDE & PUMP 50 SX CMT IF POSSIBLE.

Plugging Proposal Received By: STEVE DURRANT Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 04/05/2011 11:00 AM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

RUN TBG TO 4378' & PUMP 5 SX GEL & 40 SX CMT WITH 150# HULLS. PULL TBG TO 2150' & PUMP 230 SX CMT. CIRCULATED TO SURFACE. PULL TBG & TOPPED OFF WITH 10 SX CMT. TIED ONTO BACKSIDE & PUMPED 30 SX CMT. PRESSURED TO 500# & HELD.

Perfs:

Top	Bot	Thru	Comments
4388	4392		
4379	4382		

Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: CSG

District: 01

RECEIVED
APR 18 2011
KCC DODGE CITY

Signed Michael Maier
(TECHNICIAN)

RECEIVED
APR 28 2011
KCC WICHITA

104m CP-2/3