

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-135-22512-00-00
Spot: SWNE Sec/Twnshp/Rge: 12-19S-25W
2010 feet from N Section Line, 1970 feet from E Section Line
Lease Name: BONDURANT Well #: 1
County: NESS Total Vertical Depth: 4440 feet

Operator License No.: 31627
Op Name: WHITETAIL CRUDE, INC
Address: PO BOX 544 N HWY 283
NESS CITY, KS 67560

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	444		WITH 185 SX CMT
PROD	4.5	4435	0	WITH 100 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/14/2011 9:00 AM
Plug Co. License No.: 31627 Plug Co. Name: WHITETAIL CRUDE, INC
Proposal Rcvd. from: BILLY BRINEY Company: WHITETAIL CRUDE, INC Phone: (785) 798-3641

Proposed Plugging Method: RUN TBG TO 3700' & SPOT 35 SX CMT & 100# HULLS. PULL TBG & PERFORATE @ 1000'. PUMP 80 SX CMT OVER CASING VOLUME. IF DOES NOT CIRCULATE TIE ONTO BACKSIDE & PUMP 150 SX CMT IF POSSIBLE.

Plugging Proposal Received By: MICHAEL MAIER Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 04/14/2011 1:00 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

****MILLED ON WELL FOR 3 DAYS COULDN'T GET BELOW 3700'. RUN BOND LOG & DIDN'T FIND ANY CMT FROM 1750' TO SURFACE, DECIDED TO PLUG INSTEAD OF MAKING IT A DISPOSAL WELL.** RUN TBG TO 3700' & PUMP 50 SX CMT & 200# HULLS. PULL TBG TO 1100' & PRESSURE CASING TO 500# & HELD. FINISHED PULLING TBG & PERFORATED @ 1000'. TIED ONTO CASING & PUMPED 145 SX CMT. MAXIMUM PRESSURE WAS 600#. SHUT IN PRESSURE 300#. TIED ONTO BACKSIDE & PUMPED 40 SX CMT. PRESSURED TO 500# & HELD.**

Perfs:

Top	Bot	Thru	Comments
4394	4395		
4292	4294		

Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: TBG

District: 01

Signed

Michael Maier

(TECHNICIAN)

RECEIVED

APR 18 2011

KCC DODGE CITY

RECEIVED

APR 28 2011

KCC WICHITA