

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-113-20242-00-00
Spot: SESENWNE Sec/Twnshp/Rge: 36-21S-3W
4292 feet from S Section Line, 1651 feet from E Section Line
Lease Name: GEHRING Well #: 1
County: MCPHERSON Total Vertical Depth: 3545 feet

Operator License No.: 5399
Op Name: AMERICAN ENERGIES CORPORATION
Address: 155 N MARKET STE 710
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8	158		130 SX
PROD	4.5	3263	600	100 SX

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 04/06/2011 10:23 AM
Plug Co. License No.: 5399 Plug Co. Name: AMERICAN ENERGIES CORPORATION
Proposal Revd. from: TRAVIS HAMM Company: _____ Phone: (620) 755-2461

Proposed Plugging Method: AS PER KCC RULES AND REGULATIONS.

Plugging Proposal Received By: JEFF KLOCK Witness Type: PARTIAL
Date/Time Plugging Completed: 04/07/2011 10:23 AM KCC Agent: SHANE JONES

Actual Plugging Report:

4/6/11 AMERICAN ENERGIES DROPPED SAND. LATER THEY WENT AND TAGGED SAND @ 3072' AND CAPPED W/4 SX. THEY RIPPED CASING @ 600' AND PULLED CASING. THEY RAN DOWN TO 450' AND COPELAND SPOTTED 35 SX HOT PLUG. THEY PULLED UP TO 250' AND CIRCULATED TO SURFACE W/145 SX. COPELAND TK #37648 180 SX 60/40 POS W/4% GEL. 4/7/11 TRAVIS HAIM CALLED PLUGG DOWN 7' MIXED UP SOME CEMENT AND TOPPED IT OFF.

Perfs:

Top	Bot	Thru	Comments
3165			CSG

RECEIVED
APR 27 2011
KCC WICHITA

Remarks:

Plugged through: TBG

District: 02

Signed

(TECHNICIAN)