

TO: ✓
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-115-20605-00-00
Spot: SWNE Sec/Twnshp/Rge: 34-18S-2E
4622 feet from S Section Line, 677 feet from E Section Line
Lease Name: SCULLY H Well #: 1
County: MARION Total Vertical Depth: 2605 feet

Operator License No.: 5399
Op Name: AMERICAN ENERGIES CORPORATION
Address: 155 N MARKET STE 710
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	211		100 SX
PROD	4.5	2604	1616	100 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/08/2011 10:27 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: _____ Company: _____ Phone: _____

Proposed Plugging Method: AS PER KCC RULES AND REGULATIONS.

Plugging Proposal Received By: JEFF KLOCK Witness Type: NONE
Date/Time Plugging Completed: 04/11/2011 10:27 AM KCC Agent: SHANE JONES

Actual Plugging Report:
4/8/11 KELSO'S DROPPED SAND. 4/11/11 KELSO'S TAGGED SAND @ 2440' AND CAPPED W/4 SX. KELSO'S RIPPED CASING @ 1616'. CASING FULL OF HOLES SO KELSO'S LAID OUT CASING. THEY THEN RAN TUBING TO 250'. COPELAND TIED ON AND CIRCULATED CEMENT TO SURFACE. COPELAND TK #37654 USED 120 SX 60/40 POS W/4% GEL. 4/12/11 I CHECKED TOP PLUG. I FOUND IT DOWN APPROX 35'. COPELAND WILL TOP OFF HOLE ON 4/14/11 AFTER PLUGGING THE FUNK #2.

Perfs:

Top	Bot	Thru	Comments
2514	2524	CSG	MISSISSIPPIAN

Remarks: DENIED TA
Plugged through: TBG

RECEIVED
APR 27 2011
KCC WICHITA

District: 02

Signed [Signature]
(TECHNICIAN)

SK