

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-113-20320-00-00
Spot: NESESENE Sec/Twnshp/Rge: 23-21S-2W
2980 feet from S Section Line, 313 feet from E Section Line
Lease Name: UNRUH Well #: 1
County: MCPHERSON Total Vertical Depth: 3495 feet

Operator License No.: 5399
Op Name: AMERICAN ENERGIES CORPORATION
Address: 155 N MARKET STE 710
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP	5.5	3300		
SURF	8.625	169		150 SXS CMT
PROD	5.5	3414	525	175 SXS CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: _____
Plug Co. License No.: 5399 Plug Co. Name: AMERICAN ENERGIES CORPORATION
Proposal Rcvd. from: TRAVIS HAMM Company: _____ Phone: (620) 755-2461

Proposed Plugging Method: AS PER KCC

Plugging Proposal Received By: JEFF KLOCK Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 04/15/2011 10:35 AM KCC Agent: SHANE JONES

Actual Plugging Report:

4/14/11 AMERICAN ENERGIES DROPPED SAND. THEY LATER TAGGED SAND @2902 AND CAPPED W/5 SX. THEY RIPPED CASING @ 525'. THEY PULLED CASING UP TO 400'. 4/15/11 COPELAND OUT AT 8:15 AM TIED ON TO THE 5.5" AND BROKE CIRCULATION WITH WATER. THEY THEN MIXED UP CEMENT WITH 3 BAGS OF HULLS AND 2 SX CC. THEY CIRCULATED 325 SX TO SURFACE. AMERICAN ENERGIES STARTED TO PULL CASING, BUT THE 5.5" ELEVATORS BROKE. TRYING TO FIX ELEVATORS. THEN GOT A 4.5" SUB AND CHANGE OVER FROM 4.5" TO 5.5" AND STARTED PULLING CASING AGAIN. TRAVIS RETURNED AROUND 10:30 AM WITH ANOTHER SET OF 5.5" ELEVATORS. LANDED CASING @ 11:15 AM. COPELAND USED ANOTHER 20 SX OF TOP OFF WELL. COPELAND USED 345 SX 60/40 POS W/4% GEL. 3 BAGS HULLS AND 2 SX CC TK # 37661. 4/18/11 I CHECKED TOP PLUG DOWN 10'. AMERICAN ENERGIES TOPPING OFF.

Perfs:

Top	Bot	Thru	Comments
3338	3343	CSG	HUNTON
2986	2988	CSG	

RECEIVED
APR 27 2011
KCC WICHITA

Remarks: CIBP @ 3300'

Plugged through: CSG

District: 02

Signed _____

(TECHNICIAN)