

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-113-20466-00-01
Spot: NWNE Sec/Twnshp/Rge: 9-20S-1W
4617 feet from S Section Line, 2032 feet from E Section Line
Lease Name: VOGT'S FRED B Well #: 1
County: MCPHERSON Total Vertical Depth: 3035 feet

Operator License No.: 5399
Op Name: AMERICAN ENERGIES CORPORATION
Address: 155 N MARKET STE 710
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	163		125 SX
PROD	5.5	3035	728	75 SX

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 04/07/2011 10:20 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: _____ Company: _____ Phone: _____

Proposed Plugging Method: AS PER KCC RULES AND REGULATIONS.

Plugging Proposal Received By: JEFF KLOCK Witness Type: NONE
Date/Time Plugging Completed: 04/08/2011 10:20 AM KCC Agent: SHANE JONES

Actual Plugging Report:

4/6/11 KELSO'S DROPPED SAND. 4/7/11 KELSO'S TAGGED SAND 2940' AND CAPPED W/5 SX. KELSO'S CUT OFF CASING @ 728'. KELSO'S PULLED CASING UP TO 450' AND SPOTTED 35 SX WITH 6 BAGS HULLS AND 1% CC. THEY PULLED UP AND CIRCULATED CEMENT FROM 250' TO SURFACE USING 300 SX. COPELAND TK #37649 USED 335 SX OF 60/40 POS W/4% GEL. 4/12/11 I CHECKED TOP PLUG AND FOUND IT DOWN 4'. OPERATOR CUTTING OF CASING AND WILL BACK FILL.

Perfs:

Top	Bot	Thru	Comments
2997	3000	CSG	MISSISSIPPIAN

Remarks:

Plugged through: TBG

District: 02

Signed Jeff Klock DISTRICT SUPERVISOR
(TECHNICIAN)

RECEIVED
APR 27 2011
KCC WICHITA