

15-195-30146-00-00

Form CP-3
6-26-62

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

OCT 5 1966
10-05-1966
CONSERVATION DIVISION
WICHITA, KANSAS

Operator's Full Name Petroleum, Incorporated.

Complete Address: 300 West Douglas, Wichita, Kansas.

Lease Name Purinton Well No. 1

Location CNW-SE Sec. 32 Twp. 13 Rge. (E) 25

County Trego Total Depth 4320

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____

Plugging Contractor: Garvey Drilling Company.

Address: Route #2, Great Bend, Kansas. License No. _____

Operation Completed: Hour 1:30AM Day 29 Month 9 Year 1966

The Above well was plugged as follows:

214'--8 5/8" Surface pipe, cement circulated with 165 Sx.

Circulated hole with heavy mud, set plug @ 540' and displaced 25 Sx.

cement thru DP. Heavy mud to 210', set plug with 1/4 sack hulls and dis-

placed 20 Sx. cement thru DP. Heavy mud to 40', set plug with 1/2 sack

hulls and 10 Sx. cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: A. L. Fickel
Well Plugging Supervisor

INVOICED

DATE 10/5/66

INV. NO. 4051-W