

15-195-20142-00-00

KANSAS

Form CP-3  
Rev. 6-4-68

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 3 1969  
CONSERVATION DIVISION  
Wichita, Kansas  
11-03-1969

Operator's Full Name Birmingham-Bartlett Drilling Company,  
Complete Address 300 Kaufman Building, Wichita, Kansas.  
Lease Name Karst Well No. 1  
Location NE-SW-SE Sec. 1 Twp. 13 Rge. (E) (W) 24  
County Trego Total Depth 4525'  
Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A X  
Other well as hereafter indicated         
Plugging Contractor Red Tiger Drilling Company,  
Address 1720 Wichita Plaza Building, Wichita, Kansas. License No.         
Operation Completed: Hour 11:30 AM Day 30 Month 10 Year 1969

The above well was plugged as follows:

287'--8 5/8" Surface casing, cement circulated with 215 Sx.  
Top of Dakota section @ 750'.

Circulated hole with heavy mud. Pulled DP to 975' and displaced 100 Sx. cement thru  
DP from 975' to 650'. Pulled DP to 310' and displaced 20 Sx. cement thru DP from  
310' to 250'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to  
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

DATE 11/3/69  
INV. NO. 769-u

Signed: A. L. Nichols

Well Plugging Supervisor