

15-195-20236-00-00

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
AUG 13 1974
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Donald C. Slawson
Complete Address 408 One Twenty Bldg., Wichita, Kansas 67202
Lease Name Leverett "A" Well No. 1
Location CNE SE Sec. 36 Twp. 13 Rge. (E) (W) 22
County Trego Total Depth 4390'
Abandoned Oil Well XX Gas Well Input Well SWD Well D & A
Other well as hereafter indicated
Plugging Contractor Rockhold Engineering
Address Box 698, Great Bend, Kansas 67530 License No. 670
Operation Completed: Hour 3:45 P. Day 12 Month 8 Year 1974

The above well was plugged as follows:

Total Depth 4300' 8 5/8 csg set at 378' cwo 200 sk.
4 1/2 csg set at 4299' cw 100 sk.
4 1/2 csg PBSD 4255 with top perf. (4157)
Set 4 1/2 wood plug at 4100' -poured 50' sand -dumped 4 sx cem W/dump bailer.
Cutoff and 1800' of 4 1/2 csg.
Pumped down 8 5/8 csg with 30 sk gel & water W/100 lbs hulls -released 8 5/8 plug
and pumped 125 sk HL cem. by Halliburton. PP 250 lbs. SIP 100 lbs.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo Messing
Well Plugging Supervisor

DATE 8/14/74
INV. No. 9701-W