

15-063-20027-00-00

Form CP-3
Rev. 6-26-62

KANSAS

RP STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Woodman-Tannitti Drilling Company

Complete Address: 706 Union National Bank Building, Wichita, Kansas.

Lease Name Blackwell Well No. 1

Location CSE-SE Sec. 8 Twp. 13 Rge. (E) (W) 26

County Gove Total Depth 4530'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Above

Address: License No.

Operation Completed: Hour 9:15 AM Day 29 Month 6 Year 1968

The Above well was plugged as follows:

204'--8 5/8" Surface pipe, cement circulated with 130 Sx.
Top of Dakota section @ 875'.

Circulated hole with heavy mud. Pulled DP to 1100' and displaced 100 Sx. cement thru
DP from 1100' to 775'. Pulled DP to 215' and displaced 20 Sx. cement thru DP from
215' to 155'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 7-2-68
DIV. NO. 8048-W

RECEIVED
STATE CORPORATION COMMISSION
JUL 1 1968
CONSERVATION DIVISION
Wichita, Kansas

Signed: *W. S. Nichols*
Well Plugging Supervisor