

15-063-00110-00-00

Form CP-3
Rev. 6-26-62

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

NOV 30 1964
11-30-64
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name John O. Farmer, Incorporated,

Complete Address: 370 West Wichita, Russell, Kansas.

Lease Name Werth Well No. 1

Location SW-SW Sec. 11 Twp. 13 Rge. (E) (W) 26

County Gove Total Depth 4490

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Above

Address: License No.

Operation Completed: Hour 8:30PM Day 24 Month 11 Year 1964

The Above well was plugged as follows:

157'--8 5/8" Surface pipe, cement circulated with 115 Sx.
Circulated hole with heavy mud, set plug @ 600' and displaced 20 Sx.
cement thru DP. Heavy mud to 150', set plug with 1/2 sack hulls and
displaced 20 Sx. cement thru DP. Heavy mud to 40', set plug with 1/2
sack hulls and 10 Sx. cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

DATE 12/2/64
INV. NO. 252-W

Signed: H. L. Dechler
Well Plugging Supervisor