

State of Kansas



FORM - CP-2
Rev. 9-8-64

15-113-01390-0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

JOHN ANDERSON, Jr. Governor
WILLIAM L. MITCHELL, Chairman
AIVIN P. GRAUERHOLZ Commissioner
HARRY O. WILES Commissioner
FAYMOND B. HARVEY Secretary
ROBT. C. LONDERHOLM Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

December 6, 1964

J. P. Roberts
Adminstrator
500 Insurance Building
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION

DEC 10 1964
12-10-64
CONSERVATION DIVISION
Wichita, Kansas

Dear Sir:

Mr. Bert Self of Self Casing Pulling Co. has this

date requested permission to plug the following described well:

Mr. Self guarantees payment of the plugging fee.

Operator's full Name: Donald T. Ingling

Complete Address: 615 First Nat'l Bank Bldg., Wichita, Kansas

Lease Name: Schrag Well No. 3

Location: SW SW SE Sec. 22 Twp. 20 Rge. 3 (X) (W) X

County Mc Pherson Total Depth 3081' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Self was instructed to plug the well as follows:

Fill hole with sand to 3060' and cement with 3 sacks.

Fill hole with mud to 200'. Set rock bridge from 200' to

190' and cement hole with 20 sacks. Fill hole with mud to

40'. Set rock bridge from 40' to 30' and cement hole to

base of cellar with 10 sacks.

Very truly yours,

Conservation Division Agent