



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian  
WICHITA, KANSAS 67217

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
FEB 1 1974  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Bill Rowe of Slawson Drilling Co., Inc., has this date requested permission to plug the following described well:

Mr. Rowe guarantees payment of the plugging fee.

Operator's full Name: Donald C. Slawson,

Complete Address: 408 One-Twenty Building, Wichita, Kansas.

Lease Name: Muhlheim Well No. A-1

Location: CHE-NE-SW Sec. 24 Twp. 13 Rge. (E)(W) 22

County: Trego Total Depth 4030' Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Rowe was instructed to plug the well as follows:

235'--8 5/8" Surface casing, cement circulated with 200 Sx.  
Top of Dakota section @ 525'.

Circulate hole with heavy mud. Pull DP to 750' and displace 110 Cu. Ft. cement thru DP. Pull DP to 215' and displace 30 Cu. Ft. cement thru DP. Pull DP, set bridge @ 110' with 1 sack hulls and 10 Cu. Ft. cement to bottom of cellar.

Very truly yours,

W. L. Dickson  
Conservation Division Agent