

To: STATE CORPORATION COMMISSION  
Wichita State Office Bldg. - PLUGGING SECTION  
130 S. Market, Room 2078  
Wichita, KS 67202

API NUMBER 15- 025-20,835 ~~0000~~  
C NE , SEC. 18 , T 34 S, R 24 W/R  
3960 feet from S section line  
1320 feet from E section line

TECHNICIAN'S PLUGGING REPORT  
Operator License # 30233  
Operator: Red Hills Res. Inc.  
Name & Address: P.O. Box 205  
Englewood, KS 67840

Lease Name Theis Well # 3.  
County Clark 185.25  
Well Total Depth 5700 feet  
Conductor Pipe: Size feet  
Surface Casing: Size 8 5/8 feet 857

8-13

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ X Input Well \_\_\_\_\_ SMO Well \_\_\_\_\_ O&A \_\_\_\_\_  
Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Clarke Corporation License Number 5105  
Address P.O. Box 187, Medicine Lodge, KS

Company to plug at: Hour: 10:40 a.m. Day: 13 Month: 8 Year: 19 96

Plugging proposal received from Alan Vratil  
(company name) Clarke Corporation (phone) 316-886-5665

were: 4 1/2" at 5700' w/120 sx cement, PBD 5699', Perfs at 5483-93', Squeezed at 2400' w/350 sx cement  
1st plug set CIBP at 5400' with 2 sx cement on top,  
2nd plug run tubing to 950' and fill with cement to surface.  
Check backside.

Plugging Proposal Received by Steve Pfeifer (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 12:10 P.M. Day: 13 Month: 8 Year: 19 96

ACTUAL PLUGGING REPORT 1st plug set CIBP at 5400' with 2 sx cement on top,  
2nd plug ran tubing to 950' and circulated 80 sx cement to surface,

3rd plug pumped 25 sx cement down backside. Shut in pressure 450 psi.

RECEIVED STATE CORPORATION COMMISSION

AUG 14 1996

Remarks: Used 65/35 Pozmix 8% gel by Allied. No casing recovery.

(If additional description is necessary, use BACK of this form.)  
I did observe this plugging.

DATE: 8-16-96  
INV. NO. 46279

Signed [Signature] (TECHNICIAN)