

4 060103

7-10

15-051-06729-00-00

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-11-25-54 E-7033  
NW SW SE, SEC. 4, T. 13 S, R. 17 (W/E)

TECHNICIAN'S PLUGGING REPORT

990 feet from S section line  
2310 feet from E section line

Operator License # 8240

Lease Name Walters Well # 1

Operator: Isis Operating Co

County Ellis 116.25

Named Address Box 423

Well Total Depth 3577 feet

Russell, KS 67665

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 190

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well XXXXXX SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Co. Tools License Number \_\_\_\_\_

Address \_\_\_\_\_

Company to plug at: Hour: 1:30PM Day: 10 Month: July Year: 19 90

Plugging proposal received from Jim Line

(company name) Isis Operating Co. (phone) 913-625-4092

were: Order 50 sxs. Common and 350 sxs. 65/35 pos 8%gel and hulls

Run tubing to 1315'

7-17-90  
JUL 17 1990  
CORP. CONSERVATION DIVISION  
WICHITA, KANSAS

Plugging Proposal Received by Herb Deines

(TECHNICIAN)

Plugging Operations attended by Agent?: All XXXXXXXXXX Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 4:45PM Day: 10 Month: July Year: 19 90

ACTUAL PLUGGING REPORT 8 5/8" at 190', 5 1/2" at 3574'. Annulus squeezed between csg &

surface pipe from 800' to surface. Run tbg. to 1315'. Pmp50 sxs. Common and 260 sxs.

65/35 pos 8%gel and 600# hulls. 50#Max 50#SIP. Left tbg in hole. Tied onto annulus

between tbg and 5 1/2" and pmp90 sxs. 65/35 pos 8%gel and 400# hulls. Max 50# SIP 50#

Cement at surface next morning.

Remarks: Allied Cementing

**INVOICED**

If additional description is necessary, use BACK of this form.)

I (did XXXXXXXXXX observe this plugging.

DATE 7-24-90

INV. NO. 28715

*Herb Deines*

Signed \_\_\_\_\_ (TECHNICIAN)

Herb Deines