

4 050029

2-27

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-051-06730-00-00
SW SW SE 4 13 17
SEC. , T , S, R W/E ^{XX}

TECHNICIAN'S PLUGGING REPORT

Operator License # 8240

330 feet from S section line

2310 feet from E section line

Operator: Isis Operating Inc.

Lease Name Walters Well # 2

Name & Address Box 423

County Ellis 116.93

Russell, Ks. 67665

Well Total Depth 3598 feet

913-483-4092

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 195

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Isis Operating Inc. License Number 8240

Address

Company to plug at: Hour: Day: 27 Month: Feb Year: 19 90

Plugging proposal received from Jim Eine

(company name) (phone)

were: Order 350 sks 60/40 poz 8% gel and 500# hulls.

 Plugging Proposal Received by (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 12:30PM Day: 27 Month: FEB Year: 19 90

ACTUAL PLUGGING REPORT Fluid level at 970'. Perforated anhydrite at 1250, Dkota at

730'. Tied onto 5 1/2" casing. Pumped 50 sks 60/40 poz 8% gel pumped 175 sks 60/40

poz 8% mixed w/500# hulls mix psi 700#. Shut in psi 450#. Tied onto backside

pumped 25 sks 60/40 poz 8% gel. Hole in 8 5/8" at surface. Cement stayed at surface.

ompletion time 12:30 PM on Feb. 27, 1990 by Halliburton.

Remarks 9-1-79 had casing leak at 1075' squeezed. Ran bond log cement top at 304'.

additional description is necessary, use BACK of this form.)

3-12-90
MAR 12 1990
INVOICED

Wichita, Kansas observe this plugging.

Signed Marvin Miller (TECHNICIAN)
Marvin Miller

DATE Wichita, Kansas 3-14-90

INV. NO. 22645
2-27