

6 061899

6-29

15-051-06734-00-00

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- ~~15-0,783~~  
NW 4, SEC. 4, T 13, R 17 W/E

TECHNICIAN'S PLUGGING REPORT  
3613

4850 feet from S section line  
2970 feet from E section line

Operator License # \_\_\_\_\_  
Operator: Quinoco Petroleum Inc.  
Name & Address: Box 378111  
Denver, Co. 80237

Lease Name Wolf Well # 2  
County Ellis 11668  
Well Total Depth 3590 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 195

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well  D&A \_\_\_\_\_  
Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Halliburton Services License Number 5287  
Address Box 579 Great Bend, Ks. 67530

Company to plug at: Hour: 8:00AM Day: 29 Month: June Year: 19 89

Plugging proposal received from Aven Weaverling  
(company name) Quinoco Petroleum Inc. (phone) 913-628-3989

were: Order 50 sks common 350 sks 60/40 poz 14 sks gel 5 sks hulls.

RECEIVED  
STATE CORPORATION COMMISSION

AUG 11 1989  
8-11-89  
CONSERVATION DIVISION  
Wichita Kansas

Shot hole at 1300' and 600'  
Plugging Proposal Received by Gilbert G. Scheck  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_  
Operations Completed: Hour: 10:30AM Day: 29 Month: June Year: 19 89

ACTUAL PLUGGING REPORT 8 5/8" set at 195' w/175 sks. 5 1/2" set at 3578'

w/100 sks. D.V. from 1150' to surface. Top perf at 3295'. Pumped in 2" tubing and spotted cement from 3300' to surface. Used 50 sks common followed w/14 sks gel, followed w/5 sks hulls in 350 sks cement w/600 psi. 8 5/8" 300 psi. No cement.

Remarks: By Halliburton  
(If additional description is necessary, use BACK of this form.)

Did you observe this plugging.

Signed Gilbert G. Scheck  
(TECHNICIAN)

INVOICED  
DATE 8-16-89  
INV. NO. 25629

Gilbert G. Scheck  
FORM CP-2/3  
Rev. 01-84