

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-047-00378-00-00  
Spot: SENWSENE Sec/Twnshp/Rge: 26-25S-16W  
1953 feet from N Section Line, 677 feet from E Section Line  
Lease Name: MANTEY Well #: 3  
County: EDWARDS Total Vertical Depth: 4490 feet

Operator License No.: 5427  
Op Name: D. R. LAUCK OIL CO., INC.  
Address: 344 S LAURA  
WICHITA, KS 67211

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	338		WITH 225 SX CMT
PROD	5.5	4477	2121	WITH 800 GAL LATEX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/04/2011 9:30 AM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: JAIME HARRIS Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2537

Proposed Plugging Method: SAND TO 4250' & 5 SX CMT. PLUG AT 1050' WITH 15 SX GEL & 50 SX CMT. PLUG AT 360' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: JERRY W. STAPLETON Witness Type: PARTIAL  
Date/Time Plugging Completed: 05/04/2011 12:00 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

SANDED TO 4256' & SPOTTED 5 SX CMT WITH DUMP BAILER. 1ST PLUG AT 1050' WITH 15 SX GEL - 200# HULLS - 50 SX CMT. 2ND PLUG AT 360' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4374	4382		
4333	4356		
4306	4317		

Remarks: USED 60/40 POZMIX 4% GEL BY COPELAND ACID.

Plugged through: CSG

RECEIVED  
MAY 13 2011  
KCC WICHITA

District: 01

Signed Richard W. Lacey  
(TECHNICIAN)

RECEIVED

MAY -6 2011

KCC DODGE CITY

Form CP-2/3