

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-189-22598-00-01
Spot: S2N2NW Sec/Twnshp/Rge: 29-32S-37W
990 feet from N Section Line, 1320 feet from W Section Line
Lease Name: KUHARIC Well #: 29 #1
County: STEVENS Total Vertical Depth: 6441 feet

Operator License No.: 5278
Op Name: EOG RESOURCES, INC.
Address: 3817 NW EXPRESSWAY STE 500
OKLAHOMA CITY, OK 73112

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		5528		WITH 5 SX CMT
CIBP		5750		
CIBP		6015		
SURF	8.625	1692		WITH 480 SX CMT
PROD	4.5	6433	4027	WITH 190 SX CMT

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 04/20/2011 1:00 PM
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.
Proposal Rcvd. from: RONNIE ORR Company: ORR ENTERPRISES, INC. Phone: (580) 251-9618

Proposed Plugging Method: SET CIBP @ 5525' WITH 2 SX CMT. SHOOT 4 1/2" CASING & POOH WITH CASING. RIH W/TBG TO 1725' & SPOT 120 SX CMT. POOH TO 630' & SPOT 60 SX CMT. TOP OFF WELL @ 60' TO SURFACE WITH CMT.

Plugging Proposal Received By: STEVE DURRANT Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 04/20/2011 4:00 PM KCC Agent: JACK MACLASKEY

Actual Plugging Report:

SET CIBP @ 5528' WITH 5 SX CMT. 1ST PLUG RIH W/TBG TO 1725' & PUMP 120 SX CMT. 2ND PLUG POOH TO 630' & PUMP 60 SX CMT. 3RD PLUG AT 60' WITH 15 SX CMT.

Perfs:

Top	Bot	Thru	Comments
6048	6060		
5775	5798		
5578	5588		

Remarks: USED CLASS C CEMENT BY ORR ENTERPRISES.

Plugged through: TBG

District: 01

RECEIVED
MAY - 4 2011
KCC DODGE CITY

Signed

Jack MacLaskey
(TECHNICIAN)

RECEIVED
MAY 13 2011
KCC WICHITA