

TO: STATE CORPORATION COMMISSIO
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 6720

API Well Number: 15-073-21466-00-00
Spot: SWNWNW Sec/Twnshp/Rge: 33-23S-11E
990 feet from N Section Line, 330 feet from W Section Line
Lease Name: CARSON Well #: 16
County: GREENWOOD Total Vertical Depth: 1989 feet

Operator License No.: 6470
Op Name: SCHANKIE WELL SERVICE, INC.
Address: 1006 SW BLVD
MADISON, KS 66860

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		1930		
SURF	8.625	100		65 SX
PROD	4.5	1985		100 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/01/2011 8:00 AM
Plug Co. License No.: 6470 Plug Co. Name: SCHANKIE WELL SERVICE, INC.
Proposal Rcvd. from: SCHANKIE WELL SERVICE Company: _____ Phone: (620) 437-2595

Proposed Plugging Method: SPOT CEMENT PLUG DOWN 2 3/8" TUBING 15SK @ 1850', GEL SPACER, PERFORATE @ 800', SPOT CEMENT PLUG (15SK) @ 800', PERFORATE @ 150', SPOT CEMENT PLUG (30SK) @ 160' TO SURFACE.

Plugging Proposal Received By: MICHAEL HEFFERN WitnessType: COMPLETE (100%)
Date/Time Plugging Completed 03/01/2011 2:00 PM KCC Agent: MICHAEL HEFFERN

Actual Plugging Report:

ran tubing to 1840' pumped 15 sxs cement, pulled tubing to 800' pumped 15 sxs cement , pulled tubing to 160' pumped 55 sxs cement to surface. Shot casing @ 800' & 150' , gel spacers between cement plugs.

Perfs:

Top	Bot	Thru	Comments
1946	1950		
1898	1910		

RECEIVED

MAY 9 2011 MH

KCC Chanute Dist. #3

RECEIVED
MAY 13 2011
KCC WICHITA

Remarks:

Plugged through: TBG

District: 03

Signed Mich Heffern
(TECHNICIAN)