

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-185-22656-00-00  
Spot: SWNWSE Sec/Twnshp/Rge: 15-24S-14W  
1650 feet from S Section Line, 2310 feet from E Section Line  
Lease Name: NEILL Well #: 2  
County: STAFFORD Total Vertical Depth: 4270 feet

Operator License No.: 5030  
Op Name: VESS OIL CORPORATION  
Address: 1700 WATERFRONT PKWY BLDG 500  
WICHITA, KS 67206

| String | Size  | Depth (ft) | Pulled (ft) | Comment         |
|--------|-------|------------|-------------|-----------------|
| SURF   | 8.625 | 303        |             | WITH 200 SX CMT |
| PROD   | 4.5   | 4269       | 1612        | WITH 125 SX CMT |

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/11/2010 10:00 AM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: JAIME HARRIS Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 638-2537

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: RICHARD LACEY Witness Type: NONE  
Date/Time Plugging Completed: 11/11/2010 12:00 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

SAND TO 4000' & 4 SX CMT. 1ST PLUG AT 900' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 320' WITH 50 SX CMT. 3RD PLUG AT 60' WITH 30 SX CMT.

Perfs:

| Top  | Bot  | Thru | Comments   |
|------|------|------|------------|
| 4040 | 4048 |      | MISS CHERT |

Remarks: USED 60/40 POZMIX 4% GEL BY COPELAND.

Plugged through: TBG

District: 01

Signed

Richard W. Lacey

(TECHNICIAN)

RECEIVED

MAY - 6 2011

KCC DODGE CITY

RECEIVED  
MAY 13 2011  
KCC WICHITA

Form CP-20