

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-20291-00-00
Spot: SENWSWNW Sec/Twnshp/Rge: 10-13S-20W
3581 feet from S Section Line, 4901 feet from E Section Line
Lease Name: KING Well #: 1-V
County: ELLIS Total Vertical Depth: 3768 feet

Operator License No.: 5386
Op Name: PRODUCTION DRILLING, INC.
Address: 1023 RESERVATION RD
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3510		
SURF	8.625	252	0	150 SX
PROD	5.5	3581	0	w/unknown sxs cmt

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/10/2011 9:30 AM
Plug Co. License No.: 32128 Plug Co. Name: ROME CORPORATION DBA WESTERN WELL SERVICE
Proposal Revd. from: AVEN WEAVERLING Company: PRODUCTION DRILLING, INC. Phone: (785) 625-1189

Proposed Plugging Method: Ordered 450 sxs 60/40 pozmix - 4%gel - 500# hulls.
Perf: 2050' - 1465' - 685'.
CIPB at 3510'.

Plugging Proposal Received By: PAT STAAB Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 05/10/2011 1:30 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Ran tubing to 3400' - pumped 150 sxs cement with 300# hulls.
Pulled tubing to 2100' - pumped 150 sxs cement with 200# hulls.
Pulled tubing to 700' - pumped 40 sxs cement to circulate.
POOH. Hooked to casing and pumped 30 sxs cement.
Max. P.S.I. 100#.
Braden head dug out and found to be full of cement.

Perfs:

Top	Bot	Thru	Comments
3407	3478		LKC

Remarks: QUALITY CEMENTING SERVICES-TICKET #5344.

Plugged through: TBG

District: 04

Signed

R. D. K.

(TECHNICIAN)

RECEIVED

CM

MAY 12 2011 Form CP-2/3

KCC WICHITA

MAY 11 2011