

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-063-21907-00-00
Spot: N2NWSE Sec/Twnshp/Rge: 21-12S-31W
2475 feet from S Section Line, 1990 feet from E Section Line
Lease Name: W&E 21AD UNIT Well #: 1
County: GOVE Total Vertical Depth: 4660 feet

Operator License No.: 4767
Op Name: RITCHIE EXPLORATION, INC.
Address: 8100 E 22ND ST N # 700 BOX 783188
WICHITA, KS 67278

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	216		

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 05/06/2011 6:00 AM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Revd. from: GREG UNRUH Company: RITCHIE EXPLORATION, INC. Phone: (316) 691-9500

Proposed Plugging Method: Ordered 220 sxs 60/40 pozmix - 4% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: BRUCE RODIE Witness Type: NONE
Date/Time Plugging Completed: 05/06/2011 9:00 AM KCC Agent: BRUCE RODIE

Actual Plugging Report:

1st. Plug at 2415' w/25 sxs.
2nd. Plug at 1540' w/100 sxs.
3rd. Plug at 265' w/40 sxs.
4th. Plug at 40' w/10 sxs.
Rathole with 30 sxs.
Mousehole with 15 sxs.

Perfs:

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: DP

District: 04

Signed Bruce Rodie

(TECHNICIAN) RECEIVED

CM

MAY 12 2011 Form CP-2/3

KCC WICHITA

MAY 06 2011