

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-20367-00-01
Spot: SWNWSESE Sec/Twnshp/Rge: 24-14S-11W
696 feet from S Section Line, 1111 feet from E Section Line
Lease Name: J KRATKY Well #: 4
County: RUSSELL Total Vertical Depth: 2937 feet

Operator License No.: 9408
Op Name: TRANS PACIFIC OIL CORPORATION
Address: 100 S MAIN STE 200
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	233	0	175 SX
PROD	4.5	2937	0	250 SX

Well Type: EOR UIC Docket No: E16282.4 Date/Time to Plug: 04/26/2011 8:45 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: KEN Company: TRANS PACIFIC OIL COPORATION Phone: (785) 483-1821

Proposed Plugging Method: Ordered 375 sxs 60/40 pozmix - 4% gel - 500# hulls.
Perf: 850' - 510'.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 04/26/2011 1:30 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Ran tubing to 2790' - pumped 100 sxs cement with 300# hulls.
Pulled tubing 1150' - pumped 75 sxs cement with 100# hulls - cement circulated.
POOH. Hooked to casing and pumped 95 sxs cement - circulated out the Braden head.

Perfs:

RECEIVED
MAY 02 2011
KCC WICHITA

Remarks: QUALITY WELL SERVICE-TICKET #5184.

Plugged through: TBG

District: 04

Signed Ray A. D. Kell
(TECHNICIAN)

CM

Form CP-2/3

cc: UIC
5/12/11

APR 28 2011