

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-051-20310-00-01  
Spot: NWSESWNW Sec/Twnshp/Rge: 10-13S-20W  
3025 feet from S Section Line, 4434 feet from E Section Line  
Lease Name: KATHYRN KING Well #: 2  
County: ELLIS Total Vertical Depth: 3813 feet

Operator License No.: 5386  
Op Name: PRODUCTION DRILLING, INC.  
Address: 1023 RESERVATION RD  
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	240	0	150 SX
T1	2	3460		
PKR		3460		
PROD	5.5	3807	0	w/unknown sxs cmt

Well Type: EOR UIC Docket No: E21963.1 Date/Time to Plug: 05/10/2011 1:30 PM  
Plug Co. License No.: 32128 Plug Co. Name: ROME CORPORATION DBA WESTERN WELL SERVICE  
Proposal Rcvd. from: AVEN WEAVERLING Company: PRODUCTION DRILLING, INC. Phone: (785) 625-1189

Proposed Plugging Method: Ordered 250 sxs 60/40 pozmix - 4% gel - 500# hulls.  
Top down plug.

Plugging Proposal Received By: PAT STAAB Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 05/10/2011 3:00 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Hooked up to casing and pumped 50 sxs cement with 300# hulls - followed with 16 sxs gel - followed with 160 sxs cement with 200# hulls.  
Casing loaded pressure to 300# and squeezed off. S.I.P. 200#.  
Hooked to Braden head and pumped 5 sxs cement - pressured up to 200#.

Perfs:

Top	Bot	Thru	Comments
3479	3603		LKC

Remarks: QUALITY CEMENTING SERVICES-TICKET #5345.

Plugged through: CSG

District: 04

Signed

Ray D. Kinkel

(TECHNICIAN) RECEIVED

MAY 12 2011

Form CP-2/3

KCC WICHITA

cc: WK  
5/12/11

MAY 11 2011