

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-21752-00-01
Spot: NWSWSW Sec/Twnshp/Rge: 29-11S-18W
990 feet from S Section Line, 4950 feet from E Section Line
Lease Name: JOHNSON B OWWO Well #: 6
County: ELLIS Total Vertical Depth: 4153 feet

Operator License No.: 30606
Op Name: MURFIN DRILLING CO., INC.
Address: 250 N WATER STE 300
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	256	0	w/200 sxs cmt
PROD	5.5	4146	0	w/325 sxs cmt

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/26/2011 10:00 AM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: STAN FROETSCHNER Company: MURFIN DRILLING CO., INC. Phone: (316) 267-3241

Proposed Plugging Method: Ordered 425 sxs 60/40 pozmix - 4% gel - 400# hulls.
DV Tool at 1395' w/400 sxs.
PBTB 3656'. Junk in the hole at 2214'.

Plugging Proposal Received By: PAT STAAB Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 04/26/2011 11:30 AM KCC Agent: PAT STAAB

Actual Plugging Report:

RIH with tubing to 2210'. Quality rigged to tubing and pumped 100 sxs 60/40 pozmix - 4% gel.
Pulled tubing to 1200' - pumped 120 sxs cement with 300# hulls to circulate cement to surface.
Pulled tubing - rigged to 5 1/2" casing with a swedge and pumped 20 sxs cement.
Max. P.S.I. 300#. S.I.P. 200#.
Rigged to 8 5/8" casing - instant pressure to 200#.

Perfs:


Top	Bot	Thru	Comments
3670	4029		
3632	3636		
3595	3598		
3587	3590		

Remarks: QUALITY OILWELL CEMENTING COMPANY-TICKET #4420.

Plugged through: TBG

District: 04

Signed _____



(TECHNICIAN)

(M)

RECEIVED
MAY 02 2011
KCC WICHITA

Form CP-2/3

APR 27 2011