

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-23159-00-00
Spot: S2NESESW Sec/Twnshp/Rge: 19-15S-13W
885 feet from S Section Line, 2310 feet from W Section Line
Lease Name: BOOMHOWER Well #: 4
County: RUSSELL Total Vertical Depth: 3400 feet

Operator License No.: 32325
Op Name: POPP OPERATING, INC.
Address: 191 NE 150 RD PO BOX 187
HOISINGTON, KS 67544

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3273		
CIBP		3300		
SURF	8.625	248	0	165 SX
PROD	5.5	3397	0	160 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/21/2011 10:30 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICKEY POPP Company: POPP OPERATING, INC. Phone: (620) 786-5514

Proposed Plugging Method: Ordered 250 sxs 60/40 pozmix - 4% gel - 600# hulls - 10 sxs gel.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 04/21/2011 12:00 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Hooked up to casing - pumped 75 sxs cement with 300# hulls - followed with 10 sxs gel - followed with 135 sxs cement.
S.I.P. 100#.
Hooked up to Braden head and pumped 10 sxs cement.
Max. P.S.I. 150# - blew out casing ring.

Perfs:

Top	Bot	Thru	Comments
3302	3304		ARBUCKLE
3297	3298		ARBUCKLE
3077	3172		L-KC
3030	3034		DOUGLAS
2752	2754		TOPEKA

Remarks: QUALITY WELL SERVICE-TICKE #5147.

Plugged through: CSG

District: 04

Signed

Ray A. Dinkel

(TECHNICIAN)

CM

RECEIVED
MAY 02 2011

KCC WICHITA

APR 22 2011