

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-19188-00-00
Spot: NWNWSE Sec/Twnshp/Rge: 2-9S-16W
2310 feet from S Section Line, 2310 feet from E Section Line
Lease Name: MCFADDEN A Well #: 3
County: ROOKS Total Vertical Depth: 3315 feet

Operator License No.: 6569
Op Name: SCHMITT, CARMEN, INC.
Address: PO BOX 47
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	1344	0	w/unknown sxs cmt
PROD	4.5	3315	0	w/unknown sxs cmt

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/19/2011 9:00 AM
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.
Proposal Rcvd. from: CURTIS HITSCHMANN Company: SCHMITT, CARMEN, INC. Phone: (620) 793-2540

Proposed Plugging Method: Ordered 450 sxs 60/40 pozmix - 4% gel - 500# hulls - 8 sxs gel spacer. Perforated at 1320'.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 04/19/2011 12:45 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Ran tubing to 3156' - pumped 8 sxs gel spacer - followed with 50 sxs 60/40 pozmix - 4% gel with 200# hulls.
Pulled tubing to 1342' - pumped 385 sxs 60/40 pozmix - 4% gel with 100# hulls to circulate cement to surface on 4 1/2" casing and 8 5/8" x 4 1/2" annulus.
Pulled all tubing. Topped off 4 1/2" casing with 10 sxs 60/40 pozmix - 4% gel.

Perfs:

Top	Bot	Thru	Comments
3170	3228		KANSAS CITY

RECEIVED
MAY 02 2011
KCC WICHITA

Remarks: QUALITY OIL WELL CEMENTING-TICKETR #5043.

Plugged through: TBG

District: 04

Signed _____

Pat Bedore

(TECHNICIAN)

cm

Form CP-2/3

APR 27 2011