

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-195-20522-00-00
Spot: SESENE Sec/Twnshp/Rge: 9-13S-21W
2820 feet from S Section Line, 330 feet from E Section Line
Lease Name: KELLER A Well #: 4
County: TREGO Total Vertical Depth: 4250 feet

Operator License No.: 32278
Op Name: TENGASCO, INC.
Address: 1327 NOOSE RD PO BOX 458
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3895		
SURF	8.625	257	0	160 SX
PROD	4.5	3943	0	250 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/25/2011 9:00 AM
Plug Co. License No.: 32332 Plug Co. Name: FISCHER PIPE TESTING, INC. DBA FISCHER WELL SERVICE
Proposal Revd. from: ALAN Company: TENGASCO, INC. Phone: (865) 675-1554

Proposed Plugging Method: Ordered 350 sxs 60/40 pozmix - 4% gel - 300# hulls.
DV Tool 1602' w/550 sxs.
CIBP at 3895'.

Plugging Proposal Received By: MARVIN MILLS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 04/25/2011 2:00 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 3800' - pumped 110 sxs cement with 200# hulls.
Pulled tubing to 2445' - pumped 130 sxs cement - good circulation of cement.
Pulled tubing out - tied onto casing and squeezed with 20 sxs cement.
S.I.P. 400#.
Tied onto backside and pumped 15 sxs cement - full.

Perfs:

Top	Bot	Thru	Comments
3826	3830		
3820	3823		
3675	3678		
3668	3670		
3646	3650		
3541	3544		
3520	3524		
3470	3473		

Remarks: ALLIED CEMENTING COMPANY-TICKET #39687.

Plugged through: TBG

District: 04

Signed 
(TECHNICIAN)

CM

RECEIVED
MAY 02 2011
KCC WICHITA

Form CP-2/3

APR 26 2011