

"CORRECTED"

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-009-24361-00-00  
Spot: SWNWNE Sec/Twnshp/Rge: 18-20S-15W  
4290 feet from S Section Line, 2310 feet from E Section Line  
Lease Name: DECKERT C Well #: 2-18  
County: BARTON Total Vertical Depth: 3880 feet

Operator License No.: 33699  
Op Name: T-N-T ENGINEERING, INC.  
Address: 9250 E COSTILLA AVE #510  
GREENWOOD VLG, CO 80112

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	1057	0	425 SX
PROD	5.5	3863	1800	150 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/21/2011 2:00 PM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: RICK POPP Company: T-N-T ENGINEERING, INC. Phone: (620) 786-5514

Proposed Plugging Method: Ordered 350 sxs 60/40 pozmix - 4% gel - 500# hulls.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 03/21/2011 6:00 PM KCC Agent: BRUCE RODIE

**Actual Plugging Report:**

Sanded off perfs and topped with 5 sxs cement.  
Cut casing at 1800'.  
Pulled casing to 1600' - tied to casing and pumped 125 sxs cement with 300# hulls.  
Pulled casing to 1075' - pumped 40 sxs cement with 100# hulls.  
Pulled to 650' - pumped 60 sxs cement with 100# hulls.  
Pulled casing to 150' - circulated cement to surface with 90 sxs cement.  
Pulled casing - hole stayed full.

**Perfs:**

Top	Bot	Thru	Comments
3776	3780		
3768	3770		
3752	3754		
3746	3748		
3734	3736		

RECEIVED  
MAR 31 2011  
KCC WICHITA

Remarks: QUALITY OIL WELL CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed SEE ATTD.

(TECHNICIAN)