

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-20346-00-00
Spot: SESW Sec/Twnshp/Rge: 24-14S-11W
660 feet from S Section Line, 3300 feet from E Section Line
Lease Name: SEBESTA Well #: 3
County: RUSSELL Total Vertical Depth: 2885 feet

Operator License No.: 9408
Op Name: TRANS PACIFIC OIL CORPORATION
Address: 100 S MAIN STE 200
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	251	0	175 SX
PROD	4.5	2883	0	175 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/22/2011 1:30 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: KEN Company: TRANS PACIFIC OIL CORPORATIO Phone: (785) 483-1821

Proposed Plugging Method: Ordered 275 sxs 60/40 pozmix - 4% gel - 500# hulls.
Perf: 850' - 510'.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 04/22/2011 4:30 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Ran tubing to 2550' - pumped 100 sxs cement with 300# hulls.
Pulled tubing to 1065' - pumped 65 sxs cement with 200# hulls - cement circulated.
Braden head dug out - found full of cement.

Perfs:

Remarks: QUALITY WELL SERVICE, INC.-TICKET #5183.

Plugged through: TBG

RECEIVED
MAY 02 2011
KCC WICHITA

District: 04

Signed Ray A Dinkel
(TECHNICIAN)

CM

Form CP-2/3

APR 25 2011