

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-20222-00-00
Spot: NENESE Sec/Twnshp/Rge: 24-14S-11W
2310 feet from S Section Line, 330 feet from E Section Line
Lease Name: STOPPEL Well #: 1
County: RUSSELL Total Vertical Depth: 3180 feet

Operator License No.: 9408
Op Name: TRANS PACIFIC OIL CORPORATION
Address: 100 S MAIN STE 200
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	307	0	225 SX
PROD	5.5	2908	0	75 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/10/2011 4:30 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: GARY SHARP Company: TRANS PACIFIC OIL CORPORATIO Phone: (316) 262-3596

Proposed Plugging Method: Ordered 350 sxs 60/40 pozmix - 4% gel - 500# hulls - 3% c.c.
Trans Pacific earlier backed off casing at 350'.
Tried different times to get over and back into but couldn't.
Quality Well ran flat bottom mill, than bit, and got out of casing, but could not get back in.
Drilled down to 500' in two days.
Pulled one joint out and perforated thru tubing at 470'.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 05/09/2011 6:30 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Hooked onto tubing at 470' - pumped 80 sxs cement with 3% c.c.
Cement circulated to surface.
POOH. Hooked onto casing and pumped 5 sxs cement - circulated in cellar.
05/11/2011 - Checked fill up - down 70' - topped off with 30 sxs backside and inside of casing.
Hole stayed full.

Perfs:

Remarks: QUALITY WELL SERVICE.

Plugged through: TBG

District: 04

Signed

Ray A. Dinkel

(TECHNICIAN)

CM

RECEIVED

MAY 12 2011

Form CP-2/3

KCC WICHITA