

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-03480-00-00
Spot: E2E2SW Sec/Twnshp/Rge: 8-16S-13W
1320 feet from S Section Line, 2310 feet from W Section Line
Lease Name: BITTER H JR Well #: 5
County: BARTON Total Vertical Depth: 3386 feet

Operator License No.: 5030
Op Name: VESS OIL CORPORATION
Address: 1700 WATERFRONT PKWY BLDG 500
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	10.75	628	0	375 SX
PROD	7	3379	0	139 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/15/2011 12:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Revd. from: TRACY BLACK Company: VESS OIL CORPORATION Phone: (316) 682-1537

Proposed Plugging Method: Ordered 270 sxs 60/40 pozmix - 4% gel - 500# hulls - 6 sxs gel.

Plugging Proposal Received By: BRUCE RODIE Witness Type: NONE
Date/Time Plugging Completed: 01/18/2011 12:00 AM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Ran 2" tubing to 3000' - pumped 6 sxs gel - followed with 100 sxs cement.
Pulled tubing to 1400' - pumped 100 sxs cement.
Pulled tubing to 400' - circulated with 60 sxs cement to surface.
Pumped 5 sxs down 7" - pressured up to 300# and topped off with 5 sxs cement.

Perfs:

Top	Bot	Thru	Comments
3379	3386		ARB OH
3346	3350		SQUEEZED
3277	3285		OPEN
3175	3180		SQUEEZED

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

RECEIVED
MAY 09 2011
KCC WICHITA

District: 04

Signed Bruce Rodie
(TECHNICIAN)

CM

Form CP-2/3

APR 27 2011