

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-02154-00-00
Spot: SENESE Sec/Twnshp/Rge: 13-11S-17W
1660 feet from S Section Line, 440 feet from E Section Line
Lease Name: PEARL CRESS Well #: 2
County: ELLIS Total Vertical Depth: 3392 feet

Operator License No.: 33315
Op Name: MAR-LOU OIL CO., LLC
Address: PO BOX 218
WILSON, KS 67490

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	16	159	0	w/185 sxs cmt
COND	21	0	0	w/unknown sxs cmt
LI	6	3388	0	w/150 sxs cmt
PROD	10.75	1094	0	w/450 sxs cmt

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/09/2011 8:00 AM
Plug Co. License No.: 99998 Plug Co. Name: COMPANY TOOLS
Proposal Rcvd. from: JEFF CRAWFORD ADVANC Company: ACE WELL SERVICE Phone: (785) 885-8013

Proposed Plugging Method: Ordered 1000 sxs 60/40 pozmix - 4% gel - 700# hulls.
Perfed at 1562' - 1050' - 600'.
Junk in the hole at 1570' (possible rod box) - ran impression block.
Drilled on well two days to get to the junk in the hole.

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 05/09/2011 4:30 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Perfs:

RIH to 1550'. Allied rigged to tubing - pumped 100 sxs cement - hydraulic hose broke on bulk truck - bulk truck left for repairs.
Pulled tubing to 830'. RIH to 1000'. Allied rigged to tubing and pumped 400 sxs cement with 700# hulls mixed in.
Ran out of cement - went back for second load.
Pulled tubing to 500'. Allied rigged to tubing and pumped 430 sxs cement to circulate cement up 6" - 10 3/4" - 16" - 21" casing.
Pulled tubing. Rigged to 6" casing - pumped 25 sxs cement to pressure all casing with 300# P.S.I. S.I.P. 250#.
Cement started blowing out underside of old head on 21" casing.

Remarks: ALLIED CEMENTING COMPANY-TICKET #39698.

Plugged through: TBG

District: 04

Signed _____

(TECHNICIAN)

RECEIVED

CM

MAY 12 2011

Form CP-2/3

KCC WICHITA

MAY 10 2011