

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-23916-00-00
Spot: W2NESE Sec/Twnshp/Rge: 33-16S-13W
1980 feet from S Section Line, 990 feet from E Section Line
Lease Name: BRADSHAW Well #: 6
County: BARTON Total Vertical Depth: 3612 feet

Operator License No.: 31528
Op Name: MIKE KELSO OIL, INC.
Address: PO BOX 467
CHASE, KS 67524

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	874	0	w/425 sxs cmt
PROD	5.5	3610	2420	w/150 sxs cmt

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/09/2011 1:00 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKE KELSO OIL, INC. Phone: (620) 562-8088

Proposed Plugging Method: Ordered 350 sxs 60/40 pozmix - 4% gel - 300# hulls.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 05/09/2011 4:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Sanded off perfs and topped with 5 sxs cement.
Cut casing at 2420' - pulled casing to 1450' - tied onto casing and pumped 145 sxs cement with 300# hulls.
Pulled casing to 887' - pumped 50 sxs cement with 100# hulls.
Pulled casing to 550' - circulated cement to surface with 125 sxs cement.
Pulled casing - hole stayed full.

Perfs:

Remarks: COPELAND ACID AND CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed

Bruce Rodie

(TECHNICIAN) RECEIVED

CM

MAY 12 2011

Form CP-2/3

KCC WICHITA

MAY 10 2011