

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-009-25431-00-00  
Spot: S2SENE Sec/Twnshp/Rge: 20-17S-15W  
1290 feet from N Section Line, 330 feet from E Section Line  
Lease Name: LIMESTONE FARMS Well #: 1-20  
County: BARTON Total Vertical Depth: 3681 feet

Operator License No.: 6039  
Op Name: L. D. DRILLING, INC.  
Address: 7 SW 26TH AVE  
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	1011	0	400 SX
T1	2.865	3649		
PROD	5.5	3680	2624	200 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/25/2011 10:00 AM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: MIKE KASSELMAN Company: L.D. DRILLING, INC. Phone: (620) 793-3051

Proposed Plugging Method: Ordered 275 sxs 60/40 pozmix - 4% gel - 500# hulls.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 04/25/2011 1:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Sanded off bottom perfs and topped with 5 sxs cement.  
Cut casing at 2624' - pulled casing to 1650' - pumped 125 sxs cement with 200# hulls.  
Pulled casing to 1011' - pumped 50 sxs cement with 100# hulls.  
Pulled casing to 565' - pumped 50 sxs cement with 100# hulls.  
Pulled casing to 200' - circulated cement to surface with 75 sxs cement with 100# hulls.  
Pulled casing - hole stayed full.

Perfs:

Top	Bot	Thru	Comments
3571	3574		
3562	3566		

Remarks: COPELAND ACID AND CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed Bruce Rodie  
(TECHNICIAN)

RECEIVED  
5-2-11  
MAY 02 2011  
KCC WICHITA M

Form CP-2/3

APR 26 2011