

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-07141-00-01
Spot: SENWNW Sec/Twnshp/Rge: 9-19S-15W
990 feet from N Section Line, 990 feet from W Section Line
Lease Name: MILLER BB OWWO Well #: 1
County: BARTON Total Vertical Depth: 1905 feet

Operator License No.: 6039
Op Name: L. D. DRILLING, INC.
Address: 7 SW 26TH AVE
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	958	0	375 SX
T1	2.375	1890		
PROD	4.5	1905	1206	175 SX

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 04/28/2011 1:00 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Revd. from: MIKE KASSELMANN Company: L.D. DRILLING, INC. Phone: (620) 793-3051

Proposed Plugging Method: Ordered 275 sxs 60/40 pozmix - 4% gel - 500# hulls.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 04/28/2011 4:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Sanded off bottom perfs and topped with 5 sxs cement.
Cut casing at 1206' - pulled casing to 1200' and pumped 100 sxs cement with 200# hulls.
Pulled casing to 600' - circulated to surface with 165 sxs cement.
Pulled casing - hole stayed full.

Perfs:

Top	Bot	Thru	Comments
1882	1887		
1861	1871		

Remarks: COPELAND ACID AND CEMENTING COMPANY.

Plugged through: CSG

RECEIVED

MAY 09 2011

KCC WICHITA

District: 04

Signed Bruce Rodie
(TECHNICIAN)

CM

Form CP-2/3

APR 29 2011