

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-07134-00-01
Spot: NESENE Sec/Twnshp/Rge: 8-19S-15W
1650 feet from N Section Line, 330 feet from E Section Line
Lease Name: MILLER CC Well #: LOWWO
County: BARTON Total Vertical Depth: 2015 feet

Operator License No.: 6039
Op Name: L. D. DRILLING, INC.
Address: 7 SW 26TH AVE
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	968	0	325 SX
T1	2.375	2014		
PROD	4.5	2015	1206	200 SX

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 05/01/2011 11:00 AM
Plug Co. License No.: 31528 Plug Co. Name: MIKE KELSO OIL, INC.
Proposal Rcvd. from: MIKE KASSELMAN Company: L.D. DRILLING, INC. Phone: (620) 793-3051

Proposed Plugging Method: Ordered 275 sxs 60/40 pozmix - 4% gel - 500# hulls.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 05/01/2011 2:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Sanded off bottom perfs and topped with 5 sxs cement.
Cut casing at 1206' - pulled casing to 1190' - pumped 100 sxs cement with 200# hulls.
Pulled casing to 600' - circulated to surface with 175 sxs cement.
Pulled casing - hole stayed full.

Perfs:

Top	Bot	Thru	Comments
1886	1891		
1870	1880		

Remarks: COPELAND ACID AND CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed Bruce Rodie
(TECHNICIAN)

RECEIVED

MAY 09 2011 Form CP-2/3

KCC WICHITA

MAY 04 2011