

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-25507-00-00
Spot: NWNENE Sec/Twnshp/Rge: 8-19S-15W
330 feet from N Section Line, 990 feet from E Section Line
Lease Name: MILLER "CC" Well #: 2
County: BARTON Total Vertical Depth: 3680 feet

Operator License No.: 6039
Op Name: L. D. DRILLING, INC.
Address: 7 SW 26TH AVE
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	992	0	w/400 sxs cmt
PROD	4.5	3675	2551	w/200 sxs cmt

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/27/2011 9:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KASSELMAN Company: L.D. DRILLING, INC. Phone: (620) 793-3051

Proposed Plugging Method: Ordered 275 sxs 60/40 pozmix - 4% gel - 500# hulls.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 04/27/2011 1:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Sanded off bottom perfs and topped with 5 sxs cement.
Cut casing at 2551' - pulled casing to 1650' - pumped 125 sxs cement with 200# hulls.
Pulled casing to 1011' - pumped 50 sxs cement with 100# hulls.
Pulled casing to 565' - pumped 50 sxs cement with 100# hulls.
Pulled casing to 200' - circulated cement to surface with 105 sxs cement.
Pulled casing - hole stayed full.

Perfs:

Top	Bot	Thru	Comments
3622	3623		

Remarks: COPELAND ACID AND CEMENTING COMPANY.
Plugged through: CSG

RECEIVED
MAY 09 2011
KCC WICHITA

District: 04

Signed Bruce Rodie
(TECHNICIAN) CM

APR 29 2011