

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-25528-00-00
Spot: NWSWSW Sec/Twnshp/Rge: 6-18S-11W
990 feet from S Section Line, 330 feet from W Section Line
Lease Name: HAYDEN Well #: 1
County: BARTON Total Vertical Depth: 3510 feet

Operator License No.: 33186
Op Name: LB EXPLORATION, INC.
Address: 2135 2ND RD
HOLYROOD, KS 67450

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	370		

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 03/22/2011 12:00 AM
Plug Co. License No.: 33905 Plug Co. Name: ROYAL DRILLING INC
Proposal Revd. from: DERBY Company: LB EXPLORATION, INC. Phone: (785) 252-8034

Proposed Plugging Method: Ordered 185 sxs 60/40 pozmix - 4% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: MARVIN MILLS Witness Type: NONE
Date/Time Plugging Completed: 03/22/2011 9:00 AM KCC Agent: MARVIN MILLS

Actual Plugging Report:

1st. Plug at 3490' w/25 sxs.
2nd. Plug at 700' w/25 sxs.
3rd. Plug at 425' w/80 sxs.
4th. Plug at 40' w/10 sxs.
Rathole with 30 sxs.
Mousehole with 15 sxs.

Perfs:

Remarks: QUALITY OIL WELL CEMENTING COMPANY.

Plugged through: DP

RECEIVED

MAY 09 2011

KCC WICHITA

District: 04

Signed Marvin Mills
(TECHNICIAN)

CM

Form CP-2/3

APR 29 2011