

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-26139-00-00
Spot: N2SEWNNE Sec/Twnshp/Rge: 21-13S-19W
840 feet from N Section Line, 1650 feet from E Section Line
Lease Name: DOR-KAY "A" Well #: 1-21
County: ELLIS Total Vertical Depth: 3750 feet

Operator License No.: 5003
Op Name: MCCOY PETROLEUM CORPORATION
Address: 8080 E CENTRAL STE 300
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	220		

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 05/11/2011 12:00 AM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: ANDY DINKEL Company: MCCOY PETROLEUM CORPORATI Phone: (316) 636-2737

Proposed Plugging Method: Ordered 245 sxs 60/40 pozmix - 4% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: DAVID WANN WitnessType: NONE
Date/Time Plugging Completed: 05/11/2011 3:00 AM KCC Agent: DAVID WANN

Actual Plugging Report:

1st. Plug at 3715' w/25 sxs.
2nd. Plug at 1370' w/25 sxs.
3rd. Plug at 650' w/100 sxs.
4th. Plug at 270' w/40 sxs.
5th. Plug at 40' w/10 sxs.
Rathole with 30 sxs.
Mousehole with 15 sxs.

Perfs:

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: DP

District: 04

Signed 

(TECHNICIAN) RECEIVED

CM

MAY 12 2011 Form CP-2/3

KCC WICHITA

MAY 11 2011